


FORM C: APPENDIX II ELEVATORS

Survey Date: _____

Location Name _____
 Location Address: _____
(street address) (city) (state) (zip)

| Questions | Possible Solutions | | |
|---|--------------------------|--------------------------|---|
| | Yes | No | ► ► If no, consider making these changes: |
| 1) Are there both visible and audible door opening/closing and floor indicators? (1 tone = up, 2 tones = down.) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Install visible signals. <input type="checkbox"/> Install audible signals. |
| 2) Are the hallway call buttons located no higher than 54 inches above the floor? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Lower call buttons. <input type="checkbox"/> Provide a reach stick, permanently attached to the wall near the call button. |
| 3) Do the controls inside the elevator cab have both raised and Braille lettering next to them? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Install raised lettering and Braille in the elevator cab adjacent to all control buttons. |
| 4) Are controls mounted between 15 and 54 inches above the floor? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Move controls to within the reach range. <input type="checkbox"/> Provide reach stick, permanently attached to the elevator wall near the controls. |
| 5) Is there a sign on both doorjamb identifying each floor? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Install doorjamb signs to identify floor numbers 60 inches above the floor. Characters should be 2 inches high and provided in both raised lettering and Braille. |
| 6) Are doorjamb sign characters raised, a minimum height of 2 inches, and in Braille? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Install doorjamb signs to identify floor numbers 60 inches above the floor. Characters should be 2 inches high and provided in both raised lettering and Braille. |
| 7) Are the main entry-level floor buttons indicated with a raised star? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Install the proper indicators adjacent to the floor buttons. |
| 8) Do the elevator doors provide a clear width of at least 32 inches? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Make changes to the elevator doors to provide the necessary width. <input type="checkbox"/> Find an alternate accessible route. <input type="checkbox"/> Move to an accessible location. |

| | Yes | No | ▶ | ▶ | If no, consider making these changes: |
|---|--------------------------|--------------------------|---|---|--|
| 9) Does the elevator car provide clear floor space of a minimum depth of 54 inches and minimum width of 36 inches? (See figure at right.) | <input type="checkbox"/> | <input type="checkbox"/> | <div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 0 auto;">size</div> | | <input type="checkbox"/> Find an alternate accessible route. <input type="checkbox"/> Move to an accessible location. |
| Elevator floor space | | | | |  |
| 10) Do the elevator doors remain fully open for a minimum of 3 seconds? | <input type="checkbox"/> | <input type="checkbox"/> | <div style="border: 1px solid black; padding: 5px; width: fit-content; margin: 0 auto;">time</div> | | <input type="checkbox"/> Adjust timing of door closing.. |
| 11) Does the elevator floor stop within a maximum of ½ inch of the floor landing? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Adjust elevator car stops to correct stopping point. | | |
| 12) When the elevator car stops on each floor, is the gap between the car and the floor edge a maximum of 1-1/4 inch? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Add lip to floor landing to lessen gap. | | |
| 13) Is a two-way means of emergency communication provided that: | | | | | |
| a) is usable without voice communication (push-button activated)? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Modify communication system. | | |
| b) is identified with raised characters and Braille? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Add tactile identification with raised letters and Braille. | | |
| c) connects with emergency or authorized personnel rather than an automated system? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Modify communication system. Note: Use of a handset as part of the communication system is prohibited. | | |
| 14) Regarding any carpeting/mats, are they: | | | | | |
| d) low pile? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Replace carpeting. | | |
| e) tightly woven? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Place plywood over carpet. | | |
| f) securely attached along the edges? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Secure edges on all sides. | | |
| g) no thicker than ½ inch? | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Replace or remove mats. | | |